MINFILE Number: 082FSW195 **Name:** MASCOT (L.1344) **Status:** Prospect

Ore Zone/ Year/Report On	Tonnage/ Category	Commodity	Grade	Reference/ Comments
NORTH 1989 N	Assay/analysis Drill Core	Gold	1.4 g/t	diamond drilling on the North Mascot vein/shear zone yielded intercepts up to 1.4 grams per tonne gold over 0.7 metre in hole 89-123 Assessment Report 20158
NORTH 1989 N	Assay/analysis Drill Core	Gold	13.1 g/t	diamond drilling on the North Mascot vein/shear zone over 0.4 metre in hole 89-124 Assessment Report 20158
NORTHEAST 1989 N	Assay/analysis Rock	Gold	0.13 g/t	a sample (T005) of tailings from the shaft on the Antelope No.30 Fraction Assessment Report 19053
DRILLHOLE 1986 N	Assay/analysis Drill Core	Gold	5.5 g/t	diamond drill hole (G86.6) intercepted an augite porphyry and hornblende granodiorite with minor siltstone units hosting massive pyrrhotite lens and/or veins up to 15 centimetres; assay over over 1.5 metres Assessment Report 15432
MAIN 1986 N	Assay/analysis Grab	Gold	11.2 g/t	a grab sample (982E) of semi-massive pyrrhotite from the Main vein Assessment Report 15432
VEIN 1986 N	Assay/analysis Chip	Gold	1.8 g/t	chip sample (83143C) of silicified augite porphyry with quartz veins hosting pyrrhotite, pyrite, arsenopyrite and chalcopyrite over 1.6 metres Assessment Report 15432
MAIN 1938 N	11,612 t Probable	Gold	6.6 g/t	approximately 11612 tonnes of probable ore (above the No. 3 level) grading 6.6 grams per tonne gold from the Main vein with an additional 726 tonnes grading 14.7 grams per tonne gold from the Kapai vein Assessment Report 15432
MIDDLE D 1938 N	Assay/analysis Rock	Gold	8.6 g/t	average of surface sampling on the Middle vein Assessment Report 15432
MAIN 1938 N	Assay/analysis Rock	Gold	4.1 g/t	average of surface sampling on Main vein Assessment Report 15432
VEIN 1938 N	Assay/analysis Rock	Gold	10.3 g/t	average of surface sampling on the Kapai vein Assessment Report 15432

Ore Zone/ Year/Report On	Tonnage/ Category	Commodity	Grade	Reference/ Comments