**MINFILE Number:** 093N 101 **Name:** COL **Status:** Developed Prospect

| Ore Zone/ Year/Report On | | Tonnage/ Category | Commodity | Grade | Reference/ Comments |
|---|---|---|---|---|---|
| A<br>2007 | N | Assay/analysis<br>Drill Core | Copper<br>Silver<br>Gold | 0.588 %<br>1.9 g/t<br>0.244 g/t | Drilling highlights, in 2007, on the A zone included 0.51 per cent copper, 1.2 grams per tonne silver and 0.136 gram per tonne gold over 68 metres (34 to 102 metres down-hole) in hole 2007-01; 0.588 per cent copper, 1.9 grams per tonne silver and 0.244 gram per tonne gold over 102 metres (58 to 160 metres down-hole) in hole 2007-02; 0.270 per cent copper, 1.3 grams per tonne silver and 0.136 gram per tonne gold over 120 metres (150 to 270 metres down-hole) in hole 2007-03 and 0.562 per cent copper, 2.6 grams per tonne silver and 0.259 gram per tonne gold over 52 metres (91 to 143 metres down-hole) in hole 2007-04. Trenching and drilling on the west strike extension of the A zone yielded 0.20 per cent copper over 15 metres in trench TR-2007-1 and 0.24 per cent copper over 18 metres, including 0.41 per cent copper over 3.0 metres (112.0 to 115.0 metres down-hole) in hole 2007-7.<br>Assessment Report 30053 |
| CREEK<br>2007 | N | Assay/analysis<br>Drill Core | Copper | 0.137 % | Drilling on the Creek zone, located roughly between the main A zone and the Bug zone, yielded 0.137 and 0.158 per cent copper over 72.0 and 42.0 metres (66 to 138, 153 to 195 metres down-hole), respectively, in hole 2007-13 and 0.162 per cent copper over 9.0 metres (208.0 to 217.0 metres down-hole) in hole 2007-12<br>Assessment Report 30053 |
| NORTH<br>2007 | N | Assay/analysis<br>Drill Core | Copper | 0.19 % | Drilling on the Bug zone yielded 0.19 and 0.15 per cent copper over 35.9 and 45.0 metres in holes 2007-8 and 2007-9, respectively<br>Assessment Report 30053 |
| NORTH<br>2007 | N | Assay/analysis<br>Trench | Copper | 0.34 % | trenching on the Bug zone, to the north of the A zone, yielded up to 0.34 per cent copper over 16.7 metres, including 1.12 per cent copper over 1.2 metres in trench TR-2007-3 and 0.19 per cent copper over 6.0 metres in trench Tr-2007-4 which tested the north west strike extension of the Bug zone<br>Assessment Report 30053 |

| Ore Zone/ Year/Report On | Tonnage/ Category | Commodity | Grade | Reference/ Comments |
|---|---|---|---|---|
| A<br><br>1991 N | <br>Assay/analysis<br>Drill Core | Copper<br>Gold | 0.500 %<br>0.026 g/t | Drilling on the A zone yielded intercepts including 0.114 and 0.392 per cent copper with 0.160 and 0.057 gram per tonne gold over 3.0 and 6.0 metres (16 to 19 and 120 to 126 metres down-hole) in hole 91-2 and 0.500 per cent copper with 0.026 gram per tonne gold over 6.0 metres (42.9 to 48.9 metres down-hole) in hole 91-5, 0.386 per cent copper and 0.062 gram per tonne gold over 3.0 metres (36.5 to 39.5 metres down-hole) in hole 91-6, and 0.482 and 0.231 per cent copper with 0.026 and 0.020 gram per tonne gold, respectively, over 3.0 metres each (36.3 to 39.3 and 102.3 to 105.3 metres down-hole) in hole 91-7<br>Assessment Report 22293 |
| A<br><br>1989 Y | 1,814,200 t<br>Indicated | Copper | 0.6000 % | Drill indicated. The copper grade is only approximate due to flawed data.<br>Prospectus, Kookaburra Gold Inc., January 27, 1989 - Jenkins, May 30, 1988. |