MINFILE Number: 104B 008 **Name:** ESKAY CREEK **Status:** Past Producer

Ore Zone/ Year/Report On	Tonnage/ Category	Commodity	Grade	Reference/ Comments
OPEN PIT 2021 Y	37,654 kt Combined	Gold Silver	3.1 g/t 82.8 g/t	Pit constrained inferred measured and indicated resource using a 0.7 gram per tonne gold equivalent cut-off grade. SRK Consulting (Canada), Inc. (2021-05-21): Independent Technical Report on the Eskay Creek Au-Ag Project, Canada
OPEN PIT 2021 Y	5,239 kt Inferred	Gold Silver	1.0 g/t 25.0 g/t	Pit constrained inferred resource using a 0.7 gram per tonne gold equivalent cut-off grade. SRK Consulting (Canada), Inc. (2021-05-21): Independent Technical Report on the Eskay Creek Au-Ag Project, Canada
UNDERGROUND 2021 Y	851 kt Combined	Gold Silver	5.0 g/t 48.6 g/t	Underground measured and indicated resource using a 2.4 grams per tonne gold equivalent cut-off grade for long-hole mining and 2.8 grams per tonne gold equivalent for drift and fill mining. SRK Consulting (Canada), Inc. (2021-05-21): Independent Technical Report on the Eskay Creek Au-Ag Project, Canada
UNDERGROUND 2021 N	429 kt Inferred	Gold Silver	4.1 g/t 57.0 g/t	Underground inferred resource using a 2.4 grams per tonne gold equivalent cut-off grade for long-hole mining and 2.8 grams per tonne gold equivalent for drift and fill mining. SRK Consulting (Canada), Inc. (2021-05-21): Independent Technical Report on the Eskay Creek Au-Ag Project, Canada
ESKAY CREEK 2019-B Y	819 kt Indicated	Gold Silver	6.4 g/t 139 g/t	Underground Indicated Mineral Resource Estimate reported at a 5.0 g/t AuEq cut-Off. Preliminary Economic Assessment Report (NI 43-101 Technical Report) on Eskay Creek Project, November 7 2019, for Skeena Resources Limited.
ESKAY CREEK 2019-B Y	295 kt Inferred	Gold Silver	7.1 g/t 82 g/t	Underground Inferred Mineral Resource Estimate reported at a 5.0 g/t AuEq cut-Off. Preliminary Economic Assessment Report (NI 43-101 Technical Report) on Eskay Creek Project, November 7 2019, for Skeena Resources Limited.
ESKAY CREEK 2019-A Y	12,650 kt Indicated	Gold Silver	4.3 g/t 110 g/t	Pit constrained Indicated Mineral Resource Estimate reported at 0.7 g/t AuEq cut-off. Preliminary Economic Assessment Report (NI 43-101 Technical Report) on Eskay Creek Project, November 7 2019, for Skeena Resources Limited.
ESKAY CREEK 2019-A Y	14,420 kt Inferred	Gold Silver	2.3 g/t 47 g/t	Pit Constrained Inferred Mineral Resource Estimate reported at 0.7 g/t AuEq cut-off. Preliminary Economic Assessment Report (NI 43-101 Technical Report) on Eskay Creek Project, November 7 2019, for Skeena Resources Limited.

Ore Zone/ Year/Report On	Tonnage/ Category	Commodity	Grade	Reference/ Comments